

DRAIN-JET ROBOTICS®

MOBILE MAXIMUM-PRESSURE WATER JET AND WATER CUTTING TECHNOLOGY

APPLICATION REPORT

Removing lime deposits from concrete pipes

Customer:	Eigenbetrieb Abwasserbeseitigung Efringen-Kirchen (planned by Ingenieurbüro Bölk & Gantner GmbH)
Material of sewage pipe:	Concrete pipe
Nominal diameter:	DN 300, DN 400 and DN 600
Sewer profile:	Circular profile
Pipe length to be worked:	547 meters (different sewage lines)
Strength of deposits:	20 % to 70 %
Additional comments:	Partially strong closure und degree of hardness, only point by point use of the rinsing vehicle
Foreign bodies to be removed:	Lime deposits (sinterings)
Project duration:	15,5 working days
Average daily output:	27,3 meters



MS_1712_031_AWB_EN

Mauerspecht GmbH
An der Walze 15
01640 Coswig · Germany



www.mauerspecht.de
info@mauerspecht.de
T +49 35 23 731 46